

orm 3160-3  
August 1999)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER



FORM APPROVED  
OMB No 1004-0136  
Expires November 30, 2000

1a Type of Work <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5 Lease Serial No <b>UT ST ML-3141-A</b>
b Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6 If Indian, Allottee or Tribe Name <b>TRIBAL SURFACE</b>
2 Name of Operator <b>KERR MCGEE OIL AND GAS ONSHORE LP</b>		7 If Unit or CA Agreement, Name and No <b>UNIT #891008900A</b>
3A Address <b>1368 SOUTH 1200 EAST VERNAL, UT 84078</b>	3b Phone No (include area code) <b>(435) 781-7024</b>	8 Lease Name and Well No <b>NBU 921-16MT</b>
4 Location of Well (Report location clearly and in accordance with any State requirements *) At surface <b>SW/SW 1261'FSL, 1248'FWL 622779X 40 032247</b> At proposed prod Zone <b>44321184 -109.561019</b>		9 API Well No <b>43047-39362</b>
10 Field and Pool, or Exploratory <b>NATURAL BUTTES</b>		11 Sec, T, R, M, or Blk, and Survey or Area <b>SEC. 16, T9S, R21E</b>
12 County or Parish <b>UINTAH</b>		13 State <b>UTAH</b>
14 Distance in miles and direction from nearest town or post office* <b>10.7 +/- MILES SOUTHEAST OF OURAY, UTAH</b>		
15 Distance from proposed* location to nearest property or lease line, ft (Also to nearest drig unit line, if any) <b>1248'</b>	16 No of Acres in lease <b>280.00</b>	17 Spacing Unit dedicated to this well <b>40.00</b>
18 Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft <b>REFER TO TOPO C</b>	19 Proposed Depth <b>10,250'</b>	20 BLM/BIA Bond No on file <b>RLB0005239</b>
21 Elevations (Show whether DF, KDB, RT, GL, etc ) <b>4823'GL</b>	22 Approximate date work will start* <b>UPON APPROVAL</b>	23 Estimated duration <b>TO BE DETERMINED</b>

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No 1, shall be attached to this form

- |   |   |
|---|---|
| 1 Well plat certified by a registered surveyor  | 4 Bond to cover the operations unless covered by an existing bond on file (see Item 20 above)   |
| 2 A Drilling Plan   | 5 Operator certification  |
| 3 A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office) | 6 Such other site specific information and/or plans as may be required by the authorized office |

25 Signature 	Name (Printed/Typed) <b>SHEILA UPCHEGO</b>	Date <b>6/4/2007</b>
Title <b>SENIOR LAND ADMIN SPECIALIST</b>		
Approved by (Signature) 	Name (Printed/Typed) <b>BRADLEY G. HILL</b>	Date <b>11-08-07</b>
Title <b>ENVIRONMENTAL MANAGER</b>	Office	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon

Conditions of approval, if any, are attached


Title 18 U S C Section 1001 and Title 43 U S C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

\*(Instructions on reverse)

Federal Approval of this  
Action is Necessary

RECEIVED  
JUN 11 2007  
DIV. OF OIL, GAS & MINING

T9S, R21E, S.L.B.&M.



**LEGEND:**

- $\perp$  = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)  
 LATITUDE =  $40^{\circ}01'56.25''$  (40.032292)  
 LONGITUDE =  $109^{\circ}33'42.21''$  (109.561725)  
 (NAD 27)  
 LATITUDE =  $40^{\circ}01'56.38''$  (40.032328)  
 LONGITUDE =  $109^{\circ}33'39.73''$  (109.561036)

Kerr-McGee Oil & Gas Onshore LP


Well location, NBU #921-16MT, located as shown in the SW 1/4 SW 1/4 of Section 16, T9S, R21E, S.L.B.&M., Uintah County, Utah.

**BASIS OF ELEVATION**


TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M., TAKEN FROM THE BIG PACK MTN NE QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



**UINTAH ENGINEERING & LAND SURVEYING**  
 85 SOUTH 200 EAST - VERNAL, UTAH 84078  
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 03-31-07	DATE DRAWN: 04-06-07
PARTY D.K. M.B. P.M.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE Kerr-McGee Oil & Gas Onshore LP	

**NBU 921-16MT  
SW/SW Sec. 16, T9S, R21E  
UINTAH COUNTY, UTAH  
UT ST ML-3141-A**

**ONSHORE ORDER NO. 1**

***DRILLING PROGRAM***

**1. Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1673'
Top of Birds Nest Water	1986'
Mahogany	2358'
Wasatch	5076'
Mesaverde	8052'
MVU2	8983'
MVL1	9557'
TD	10,250'

**2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1673'
	Top of Birds Nest Water	1986'
	Mahogany	2358'
	Wasatch	5076'
Gas	Mesaverde	8052'
Gas	MVU2	8983'
Gas	MVL1	9557'
Gas	N/A	
Water	N/A	
Other Minerals		

**3. Pressure Control Equipment (Schematic Attached)**

*Please see the Natural Buttes Unit Standard Operating Procedure (SOP).*

**4. Proposed Casing & Cementing Program:**

*Please see the Natural Buttes Unit SOP.*

**5. Drilling Fluids Program:**

*Please see the Natural Buttes Unit SOP.*

**6. Evaluation Program:**

*Please see the Natural Buttes Unit SOP.*

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 10,250' TD, approximately equals 6355 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 4100 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

*Drilling is planned to commence immediately upon approval of this application.*

9. **Variances:**

*Please see Natural Buttes Unit SOP.*


10. **Other Information:**

*Please see Natural Buttes Unit SOP.*



# **KERR-McGEE OIL & GAS ONSHORE LP** **DRILLING PROGRAM**

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE May 31, 2007  
WELL NAME NBU 921-16MT TD 10,250' MD/TVD  
FIELD Natural Buttes COUNTY Uintah STATE Utah ELEVATION 4,823' GL KB 4,838'  
SURFACE LOCATION SWSW, SEC 16-T9S-R21E, 1261' FSL 1248' FWL BHL Straight Hole  
Latitude: 40.032292 Longitude: 109.561725  
OBJECTIVE ZONE(S) Wasatch/Mesaverde  
ADDITIONAL INFO Regulatory Agencies: TRIBAL SURF & BLM MINERALS, UDOGM, Tri-County Health Dept.





# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

## CASING PROGRAM

	WT	WT	WT	WT	WT	WT	WT	WT
	WT	WT	WT	WT	WT	WT	WT	WT
CONDUCTOR	14"	0-40'						
SURFACE	9-5/8"	0 to 2200	32.30	H-40	STC	0.58	1.33	3.45
	9-5/8"	2200 to 2600	36.00	J-55	STC	1.11	1.66	7.67
PRODUCTION	4-1/2"	0 to 10250	11.60	I-80	LTC	1.93	1.01	1.94

1) Max Anticipated Surf. Press. (MASP) (Surface Casing) = (Pore Pressure at next csg point - (0.22 psi/ft - partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft - partial evac gradient x TD)

.22 psi/ft = gradient for partially evac wellbore

(Burst Assumptions: TD = 11.8 ppg)

(Tension Assumptions: Air Weight of Casing "Buoy. Fact. of water)

(Collapse Assumption: Fully Evacuated Casing, Max MW)

MASP 4034 psi

Burst SF is low but csg is stronger than formation at 2600 feet

EMW @ 2600 for 2270# is 16.8 ppg or 0.9 psi/ft

## CEMENT PROGRAM

	WT	WT	WT	WT	WT	WT	WT
	WT	WT	WT	WT	WT	WT	WT
SURFACE	LEAD	500	Premium cmt + 2% CaCl	215	60%	15.60	1.18
			+ 25 pps floccle				
Option 1							
	TOP OUT CMT (1)	250	20 gals sodium silicate + Premium cmt	100		15.60	1.18
			+ 2% CaCl + 25 pps floccle				
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE	LEAD	2000	Prem cmt + 16% Gel + 10 pps gilsonite	230	35%	11.00	3.82
Option 2			+ 25 pps Floccle + 3% salt BWOC				
	TAIL	500	Premium cmt + 2% CaCl	180	35%	15.60	1.18
			+ 25 pps floccle				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,570'	Premium Lite II + 3% KCl + 0.25 pps	500	60%	11.00	3.38
			cellofacke + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	5,680'	50/50 Poz/G + 10% salt + 2% gel	1590	60%	14.30	1.31
			+ 1% R-3				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

## FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

## ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper

& lower kelly valves.

Drop Tolco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE:


DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

NBU 921-16MT DHD

# 5M BOP STACK and CHOKE MANIFOLD SYSTEM



**NBU 921-16MT  
SW/SW SEC. 16, T9S, R21E  
UINTAH COUNTY, UTAH  
UT ST ML-3141-A**

**ONSHORE ORDER NO. 1**

***MULTI-POINT SURFACE USE & OPERATIONS PLAN***

**1. Existing Roads:**

Refer to the attached location directions.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

**2. Planned Access Roads:**

*Please see the Natural Buttes Unit Standard Operating Procedure (SOP).*

Approximately 40' +/- of new access road is proposed. Please refer to the attached Topo Map B.

**3. Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities:**

*Please see the Natural Buttes Unit SOP.*

Approximately 346' +/- of 4" steel pipeline is proposed from the location to an existing pipeline. Refer to the attached Topo Map D.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The requested color is Carlsbad Canyon Brown (2.5Y 6/2), a non-reflective earthtone.

**5. Location and Type of Water Supply:**

*Please see the Natural Buttes SOP.*

**6. Source of Construction Materials:**

*Please see the Natural Buttes SOP.*

**7. Methods of Handling Waste Materials:**

*Please see the Natural Buttes SOP.*

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E (*Request is in lieu of filing Form 3160-5, after initial production*).



8. **Ancillary Facilities:**

*Please see the Natural Buttes SOP.*

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

Culverts will be installed where needed.

A run off diversion for drainage will be constructed where needed.

The reserve pit will be lined. When the reserve pit is closed the pit liner will be buried below plow depth.

Location size may change prior to the drilling of the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling rig. The location will be re-surveyed and a form 3160-5 will be submitted.

10. **Plans for Reclamation of the Surface:**

*Please see the Natural Buttes SOP.*

11. **Surface Ownership:**

The well pad and access road are located on lands owned by:

Ute Indian Tribe  
P.O. Box 70  
Fort Duchesne, Utah 84026  
(435) 722-5141

12. **Other Information:**

A Class III Archaeological Survey Report has been conducted for this location and submitted to the Ute Indian Tribe prior to the on-site inspection.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it within 460' of any non-committed tract lying within boundaries of the unit.

**13. Lessee's or Operator's Representative & Certification:**

Sheila Upchego  
Senior Land Admin Specialist  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East  
Vernal, UT 84078  
(435) 781-7024

Randy Bayne  
Drilling Manager  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East  
Vernal, UT 84078  
(435) 781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under the terms and conditions of the lease for the operations conducted upon leased lands.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Indian Affairs Nationwide Bond #RLB0005239, Bureau of Land Management Nationwide Bond #WYB000291 and State of Utah Bond #RLB0005237.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

  
Sheila Upchego

6/4/2007

Date

# Kerr-McGee Oil & Gas Onshore LP

NBU #921-16MT

SECTION 16, T9S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; TURN LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 3.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 2.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 40' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 41.7 MILES.

# Kerr-McGee Oil & Gas Onshore LP

NBU #921-16MT

LOCATED IN UINTAH COUNTY, UTAH

SECTION 16, T9S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHWESTERLY




PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


04 04 07  
MONTH DAY YEAR

PHOTO

TAKEN BY: D.K.

DRAWN BY: C.P.

REVISED: 00-00-00



# LEGEND:

○ PROPOSED LOCATION

Kerr-McGee Oil & Gas Onshore LP

NBU #921-16MT

SECTION 16, T9S, R21E, S.L.B.&M.

1261' FSL 1248' FWL



Uintah Engineering & Land Surveying  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



TOPOGRAPHIC  
 MAP


04 04 07  
 MONTH DAY YEAR

SCALE: 1:100,000

DRAWN BY: C.P.

REVISED: 00-00-00





# LEGEND:

EXISTING ROAD



Utah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



Kerr-McGee Oil & Gas Onshore LP

NBU #921-16MT

SECTION 16, T9S, R21E, S.L.B.&M.

1261' FSL 1248' FWL

TOPOGRAPHIC  
MAP

04 04 07  
MONTH DAY YEAR

SCALE: 1" = 2000'

DRAWN BY: C.P.

REVISED: 00-00-00

B  
TOPO

T9S

R  
21  
E

PROPOSED LOCATION:  
NBU #921-16MT

## LEGEND:

- |                   |                         |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS  | ○ WATER WELLS           |
| ● PRODUCING WELLS | ● ABANDONED WELLS       |
| ● SHUT IN WELLS   | ● TEMPORARILY ABANDONED |



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

N

Kerr-McGee Oil &amp; Gas Onshore LP

NBU #921-16MT  
SECTION 16, T9S, R21E, S.L.B.&M.  
1261' FSL 1248' FWL


TOPOGRAPHIC  
MAP

04 04 07  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00

C  
TOPO





APPROXIMATE TOTAL PIPELINE DISTANCE = 346' +/-

# **LEGEND:**

————— EXISTING PIPELINE  
 - - - - - PROPOSED PIPELINE



**Kerr-McGee Oil & Gas Onshore LP**

**NBU #921-16MT**

**SECTION 16, T9S, R21E, S.L.B.&M.**

**1261' FSL 1248' FWL**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC  
 MAP**

**04 04 07**  
 MONTH DAY YEAR

**SCALE: 1"=1000'**

**DRAWN BY: C.P.**

**REVISED: 00-00-00**

**D  
 TOPO**



# Kerr-McGee Oil & Gas Onshore LP

NBU #921-16MT

PIPELINE ALIGNMENT

LOCATED IN UINTAH COUNTY, UTAH

SECTION 16, T9S, R21E, S.L.B.&M.




PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: NORTHEASTERLY




PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS

04 04 07  
MONTH DAY YEAR

PHOTO

TAKEN BY: L.K.

DRAWN BY: C.P.


REVISED: 00-00-00

# Kerr-McGee Oil & Gas Onshore LP

FIGURE #1

## LOCATION LAYOUT FOR

NBU #921-16MT  
SECTION 16, T9S, R21E, S.L.B.&M.  
1261' FSL 1248' FWL



SCALE: 1" = 50'  
DATE: 04-06-07  
Drawn By: P.M.

F-2.2'  
El. 21.1'

CONSTRUCT DIVERSION DITCH

Approx.  
Top of  
Cut Slope  
C-0.3'  
El. 23.6'

Sta. 3+50

### NOTE:

Flare Pit is to be located  
a min. of 100' from the  
Well Head.

Approx.  
Toe of  
Fill Slope

Pit Topsoil

FLARE PIT C-0.1'  
El. 23.4'

Bloole Line

El. 21.3'  
C-8.0'  
(btm. pit)

Reserve Pit Backfill  
& Spoils Stockpile

15' WIDE DIKE

RESERVE PITS  
(10' Deep)  
Total Pit Capacity  
W/2' of Freeboard  
= 9,850 Bbls. ±  
Total Pit Volume  
= 2,780 Cu. Yds.

Sta. 0+45

El. 19.8'  
C-6.5'  
(btm. pit)

15' WIDE DIKE

Existing Pipeline

F-0.4'  
El. 22.9'

MUD TANKS

PUMP HOUSE

TRASH

PROPEANE STORAGE

F-2.3'  
El. 21.0'

A

30'

4

F-3.9'  
El. 19.4'

PIPE TUBS

CATWALK

PIPE RACKS

C-0.2'  
El. 23.5'

RIG

Existing Well  
Head CIGE #19

DOG HOUSE

LIGHT PLANT

BOILER

COMPRESSOR

BOOSTER

Separator

Berm

Tank

Existing Pipeline

Proposed Access Road

Meter

Meth. Tank

Separator

Existing Road

1

F-0.6'  
El. 22.7'

Sta. 1+70

2

F-2.6'  
El. 20.7'

3

F-2.6'  
El. 20.7'

### LINE TABLE

LINE	BEARING	LENGTH
L1	S28°28'19"W	26.92'

### NOTES:

Elev. Ungraded Ground At Loc. Stake = 4823.5'  
FINISHED GRADE ELEV. AT LOC. STAKE = 4823.3'

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

# Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

## TYPICAL CROSS SECTIONS FOR

NBU #921-16MT


SECTION 16, T9S, R21E, S.L.B.&M.

1261' FSL 1248' FWL

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 04-06-07

Drawn By: P.M.



### NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

### \* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

### APPROXIMATE YARDAGES

CUT  
(12") Topsoil Stripping = 1,580 Cu. Yds.  
(New Construction Only)  
Remaining Location = 2,150 Cu. Yds.  
  
TOTAL CUT = 2,730 CU.YDS.  
FILL = 3,260 CU.YDS.

EXCESS MATERIAL = 470 Cu. Yds.  
Topsoil & Pit Backfill = 2,970 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS DEFICIT = <2,500> Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 06/11/2007

API NO. ASSIGNED: 43-047-39362

WELL NAME: NBU 921-16MT

OPERATOR: KERR-MCGEE OIL & GAS ( N2995 )

PHONE NUMBER: 435-781-7024

CONTACT: SHEILA UPCHEGO

**PROPOSED LOCATION:**

SWSW 16 090S 210E

SURFACE: 1261 FSL 1248 FWL

BOTTOM: 1261 FSL 1248 FWL

COUNTY: UINTAH

LATITUDE: 40.03225 LONGITUDE: -109.5610

UTM SURF EASTINGS: 622779 NORTHINGS: 4432118

FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DKD	11/8/07
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-3141-A

SURFACE OWNER: 2 - Indian

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

**RECEIVED AND/OR REVIEWED:**

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. 22013542 )  
☒ Potash (Y/N)  
☒ Oil Shale 190-5 (B) or 190-3 or 190-13  
☒ Water Permit  
(No. 43-8496 )  
☒ RDCC Review (Y/N)  
(Date: )  
☒ Fee Surf Agreement (Y/N)  
☒ Intent to Commingle (Y/N)

**LOCATION AND SITING:**

\_\_\_ R649-2-3.  
Unit: NATURAL BUTTES  
\_\_\_ R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells  
\_\_\_ R649-3-3. Exception  
☒ Drilling Unit  
Board Cause No: 173-14  
Eff Date: 12-2-09  
Siting: 460' to 1/2 mile E of Indian Trust  
\_\_\_ R649-3-11. Directional Drill

COMMENTS:

*Sup, Separate H/W*

STIPULATIONS:

*1- Federal Assurance  
2- Oil Shale  
3- STATEMENT OF BASIS  
4- Surface Csg Cont Stip*

CICE 44

PREPARED BY: DIANA MASON  
DATE: 14-JUNE-2007

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** KERR-MCGEE OIL & GAS ONSHORE, LP  
**Well Name** NBU 921-16MT  
**API Number** 43-047-39362-0 **APD No** 500 **Field/Unit** NATURAL BUTTES  
**Location:** 1/4,1/4 SWSW **Sec** 16 **Tw** 9S **Rng** 21E 1261 FSL 1248 FWL  
**GPS Coord (UTM)** **Surface Owner**

### **Participants**

### **Regional/Local Setting & Topography**

### **Surface Use Plan**

**Current Surface Use**

**New Road**

**Miles**

**Well Pad**

**Width**

**Length**

**Src Const Material**

**Surface Formation**

**Ancillary Facilities**

### **Waste Management Plan Adequate?**

### **Environmental Parameters**

**Affected Floodplains and/or Wetland**

**Flora / Fauna**

**Soil Type and Characteristics**

**Erosion Issues**

**Sedimentation Issues**

**Site Stability Issues**

**Drainage Diversion Required**

**Berm Required?**

**Erosion Sedimentation Control Required?**

**Paleo Survey Run?**

**Paleo Potential Observed?**

**Cultural Survey Run?**

**Cultural Resources?**

### **Reserve Pit**

# Application for Permit to Drill

## Statement of Basis

8/9/2007

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Ownr</b>	<b>CBM</b>
500	43-047-39362-00-00		GW	I	No
<b>Operator</b>	KERR-MCGEE OIL & GAS ONSHORE, LP		<b>Surface Owner-APD</b>		
<b>Well Name</b>	NBU 921-16MT	<b>Unit</b>	NATURAL BUTTES		
<b>Field</b>	NATURAL BUTTES	<b>Type of Work</b>			
<b>Location</b>	SWSW 16 9S 21E S 1261 FSL 1248 FWL GPS Coord (UTM) 622779E 4432118N				

### Geologic Statement of Basis

Kerr McGee proposes to set 2,600' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 300'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 16. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed surface casing and cement should adequately protect ground water in this area.

Brad Hill  
APD Evaluator

8/9/2007  
Date / Time

### Surface Statement of Basis

The surface rights at the proposed location are owned by the Ute Indian Tribe. The operator is responsible for obtaining all required permits and rights-of-way prior to making any surface disturbance or drilling the well.

Brad Hill  
Onsite Evaluator

8/9/2007  
Date / Time

### Conditions of Approval / Application for Permit to Drill

<b>Category</b>	<b>Condition</b>
	None.

**Site-Specific Factors****Site Ranking**

**Distance to Groundwater (feet)**  
**Distance to Surface Water (feet)**  
**Dist. Nearest Municipal Well (ft)**  
**Distance to Other Wells (feet)**  
**Native Soil Type**  
**Fluid Type**  
**Drill Cuttings**  
**Annual Precipitation (inches)**  
**Affected Populations**  
**Presence Nearby Utility Conduits**

**Final Score****Sensitivity Level****Characteristics / Requirements****Closed Loop Mud Required?****Liner Required?****Liner Thickness****Pit Underlayment Required?****Other Observations / Comments**

Brad Hill  
**Evaluator**


8/9/2007  
**Date / Time**



pair to PPG

# 2007-06 Kerr McGee NBU 921-16MT

## Casing Schematic



Well name:	<b>2007-06 Kerr McGee NBU 921-16MT</b>	
Operator:	<b>Kerr McGee Oil &amp; Gas Onshore L.P.</b>	
String type:	<b>Surface</b>	Project ID: <b>43-047-39362</b>
Location:	<b>Uintah County, Utah</b>	

**Design parameters:**
**Collapse**

Mud weight: 8.300 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 111 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,400 ft

Cement top: 880 ft

**Burst**

Max anticipated surface pressure: 2,288 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 2,600 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 2,281 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 10,250 ft  
Next mud weight: 11.800 ppg  
Next setting BHP: 6,283 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,600 ft  
Injection pressure: 2,600 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2600	9.625	36.00	J-55	ST&C	2600	2600	8.796	1128.6
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1121	2020	1.802	2600	3520	1.35	82	394	4.80 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357  
FAX: (801) 359-3940

Date: June 29, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 2600 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2007-06 Kerr McGee NBU 921-16MT</b>	
Operator:	<b>Kerr McGee Oil &amp; Gas Onshore L.P.</b>	
String type:	Production	Project ID: 43-047-39362
Location:	Uintah County, Utah	

**Design parameters:**
**Collapse**

Mud weight: 11.800 ppg  
 Internal fluid density: 2.300 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
 Surface temperature: 75 °F  
 Bottom hole temperature: 218 °F  
 Temperature gradient: 1.40 °F/100ft  
 Minimum section length: 1,500 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 4,028 psi  
 Internal gradient: 0.220 psi/ft  
 Calculated BHP 6,283 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
 8 Round LTC: 1.80 (J)  
 Buttress: 1.60 (J)  
 Premium: 1.50 (J)  
 Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 8,442 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	10250	4.5	11.60	I-80	LT&C	10250	10250	3.875	894.5
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	5058	6360	1.257	6283	7780	1.24	98	212	2.16 J

Prepared Helen Sadik-Macdonald  
 by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357  
 FAX: (801) 359-3940

Date: August 29, 2007  
 Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 10250 ft, a mud weight of 11.8 ppg. An internal gradient of .119 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

### IN REPLY REFER TO:

3160

(UT-922)

June 18, 2007

### Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2007 Plan of Development Natural Buttes Unit Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2007 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ Wasatch/MesaVerde)

43-047-39375	NBU 1021-05MT	Sec 05 T10S R21E 0745 FSL 0529 FWL
43-047-39376	NBU 1021-11I	Sec 11 T10S R21E 2387 FSL 1247 FEL
43-047-39377	NBU 1021-11O	Sec 11 T10S R21E 1192 FSL 2437 FEL
43-047-39378	NBU 1021-11N	Sec 11 T10S R21E 1258 FSL 1861 FWL
43-047-39379	NBU 1021-11P	Sec 11 T10S R21E 0232 FSL 1170 FEL
43-047-39380	NBU 1021-11M	Sec 11 T10S R21E 0425 FSL 1318 FWL
43-047-39381	NBU 1021-11J	Sec 11 T10S R21E 2252 FSL 2402 FEL
43-047-39383	NBU 1021-12A	Sec 12 T10S R21E 0835 FNL 0781 FEL
43-047-39382	NBU 1021-12M	Sec 12 T10S R21E 1022 FSL 0329 FWL
43-047-39384	NBU 1021-12N	Sec 12 T10S R21E 0677 FSL 2302 FWL
43-047-39385	NBU 1021-12K	Sec 12 T10S R21E 1532 FSL 1952 FWL
43-047-39386	NBU 1021-12L	Sec 12 T10S R21E 1580 FSL 0196 FWL
43-047-39360	NBU 921-16J	Sec 16 T09S R21E 1994 FSL 1660 FEL
43-047-39361	NBU 921-16HT	Sec 16 T09S R21E 1858 FNL 1013 FEL
43-047-39362	NBU 921-16MT	Sec 16 T09S R21E 1261 FSL 1248 FWL
43-047-39363	NBU 921-17K	Sec 17 T09S R21E 2147 FSL 1635 FWL
43-047-39364	NBU 921-17J	Sec 17 T09S R21E 1508 FSL 1748 FEL
43-047-39365	NBU 921-20M	Sec 20 T09S R21E 0568 FSL 0586 FWL
43-047-39366	NBU 921-20O	Sec 20 T09S R21E 1026 FSL 1859 FEL
43-047-39367	NBU 921-23C	Sec 23 T09S R21E 0817 FNL 1945 FWL
43-047-39368	NBU 921-25NT	Sec 25 T09S R21E 1150 FSL 2607 FWL
43-047-39369	NBU 922-18O	Sec 18 T09S R22E 1255 FSL 2083 FEL

Page 2

43-047-39370 NBU 922-18I Sec 18 T09S R22E 1600 FSL 0901 FEL  
43-047-39371 NBU 922-18G Sec 18 T09S R22E 2009 FNL 1936 FEL  
43-047-39372 NBU 922-20E Sec 20 T09S R22E 2182 FNL 0452 FWL  
43-047-39387 NBU 1022-6B-2 Sec 06 T10S R22E 0160 FNL 2289 FEL  
43-047-39389 NBU 1022-24B Sec 24 T10S R22E 1035 FNL 1619 FEL  
43-047-39374 NBU 1020-24BT Sec 24 T10S R20E 0914 FNL 1966 FEL  
43-047-39373 NBU 1020-01KT Sec 01 T10S R20E 1731 FSL 1834 FWL

Our records indicate the NBU 1022-24B is closer than 460 feet from the Natural Buttes Unit boundary.

We have no objections to permitting the wells so long as the unit operator receives an exception to the locating and siting requirements of the State of Utah (R649-3-2).

/s/ Michael L. Coulthard

bcc: File – Natural Buttes Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:6-18-07

**Helen Sadik-Macdonald - Surface Casing changes**

---

**From:** "Laney, Brad"  
**To:**  
**Date:** 09/07/2007 3:26 PM  
**Subject:** Surface Casing changes  
**CC:** "Upchego, Sheila" , "Worthen, Rebecca"

---

Helen,

The following wells will have 36# casing run in them for the entire surface casing interval.

NBU 921-16P  
NBU 921-16J  
NBU 921-16HT  
NBU 921-16MT  
NBU 921-25NT  
NBU 921-34MT

Anadarko is currently in the process of converting all future wells to a 36# surface casing string but we will continue to utilize our existing inventory of 32.3# until sometime in October. All future permits will reflect the changes to the surface casing. If you need any additional paperwork or have any questions, let me know.

Thanks again  
Brad

---

**Anadarko Confidentiality Notice: This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. If you have received this communication in error, please immediately notify sender by return e-mail and destroy the communication. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited.**



JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil Gas and Mining

JOHN R. BAZA  
Division Director

November 8, 2007

Kerr McGee Oil and Gas Onshore LP  
1368 S 1200 East  
Vernal, UT 84078

Re: NBU 921-16MT Well, 1261' FSL, 1248' FWL, SW SW, Sec. 16, T. 9 South, R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39362.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor  
Bureau of Land Management Vernal Office  
SITLA



Operator: Kerr McGee Oil and Gas Onshore LP  
Well Name & Number NBU 921-16MT  
API Number: 43-047-39362  
Lease: ML-3141-A

Location: SW SW Sec. 16 T. 9 South R. 21 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office (801) 942-0873 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.



4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. Surface casing shall be cemented to the surface.
8. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

## DIVISION OF OIL, GAS AND MINING

### **SPUDDING INFORMATION**

Name of Company: KERR-McGEE OIL & GAS ONSHORE, L.P.

Well Name: NBU 921-16MT

Api No: 43-047-39362 Lease Type: STATE-INDIAN SURF

Section 16 Township 09S Range 21E County UINTAH

Drilling Contractor PETE MARTIN DRLG RIG # RATHOLE

### **SPUDDED:**

Date 08/11/08

Time 10:00 AM

How DRY

**Drilling will Commence:** \_\_\_\_\_

Reported by LEW WELDON

Telephone # (435) 828-7035

Date 08/12/08 Signed CHD

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

## ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995  
Address: 1368 SOUTH 1200 EAST  
city VERNAL  
state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304739362	NBU 921-16MT		SWSW	16	9S,	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	8/11/2008			<u>8/14/08</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 08/11/2008 AT 10:00 AM.							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA UPCHEGO

Name (Please Print)

Signature

REGULATORY ANALYST

8/11/2008

Title

Date

**RECEIVED**

**AUG 11 2008**

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTSTML-3141-A
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: TRIBAL SURFACE
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1261'FSL, 1248'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S, 21E		8. WELL NAME and NUMBER: NBU 921-16MT 9. API NUMBER: 4304739362 10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: WELL SPUD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 08/11/2008 AT 10:00 AM.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 8/11/2008

(This space for State use only)

RECEIVED  
AUG 13 2008  
DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTSTML-3141-A
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: TRIBAL SURFACE
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1261'FSL, 1248'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S, 21E		8. WELL NAME and NUMBER: NBU 921-16MT 9. API NUMBER: 4304739362 10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: SET SURFACE CSG
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PROPETRO AIR RIG ON 08/12/2008. DRILLED 12 1/4" SURFACE HOLE TO 2760'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/250 SX HIFILL CLASS G @11.0 PPG 3.82 YIELD. TAILED CMT W/200 SX PREM CLASS G @15.8 PPG 1.15 YIELD GOOD RETURNS THROUGH OUT JOB 17 +/- BBLS LEAD CMT TO PIT. RAN 200' OF 1" PIPE. CMT W/125 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN 1" PIPE GOOD CMT TO SURFACE AND FELL BACK. TOP OUT W/85 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 8/18/2008

(This space for State use only)

RECEIVED

AUG 20 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
KERR MCGEE OIL & GAS ONSHORE LP

3. ADDRESS OF OPERATOR:  
1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078

PHONE NUMBER:  
(435) 781-7024

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1261' FSL, 1248' FWL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S 21E

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
UTSTML-3141-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
TRIBAL SURFACE

7. UNIT or CA AGREEMENT NAME:  
UNIT #891008900A

8. WELL NAME and NUMBER:  
NBU 921-16MT

9. API NUMBER:  
4304739362

10. FIELD AND POOL, OR WILDCAT:  
NATURAL BUTTES

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: FINAL DRILLING OPERATIONS
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

FINISHED DRILLING FROM 2760' TO 10310' ON 10/21/2008. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/1370 SX PREM LITE II @11.5 PPG 2.82 YIELD. TAILED CMT W/309 SX 50/50 POZ @14.3 PPG 1.31 YIELD. DISPLACE W/150 BBLS CLAY TREAT NO RETURNS DURING JOB UNTIL START OF DISPLACEMENT 29 BBLS CMT BACK BUMP PLUG @3550 PSI HELD. NIPPLE DOWN SET SLIPS W/70K CUT OFF CSG. CLEAN PITS.

RELEASED PIONEER RIG 41 ON 10/21/2008 AT 0600 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 10/22/2008

(This space for State use only)

RECEIVED

OCT 27 2008

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL	OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: UTSTML-3141-A
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: TRIBAL SURFACE
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 921-16MT
4. LOCATION OF WELL		9. API NUMBER: 4304739362
FOOTAGES AT SURFACE: 1261' FSL, 1248' FWL		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S 21E		COUNTY: UINTAH
		STATE: UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: PRODUCTION
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	START-UP

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 11/9/2008 AT 1030 HRS.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE <i>Sheila Upchego me</i>	DATE 11/10/2008

(This space for State use only)

RECEIVED  
NOV 12 2008

Wins No.: 94956

NBU 921-16MT

## Well Operations Summary Long

Operator KERR MCGEE OIL & GAS ONSHORE LP	FIELD NAME NATURAL BUTTES	SPUD DATE 08/12/2008	GL 4,823	KB 4823	ROUTE V23
API 4304739362	STATE UTAH	COUNTY UINTAH	DIVISION ROCKIES		
Long/Lat.: 40.03229 / -109.56173	Q-Q/Sect/Town/Range: SWSW / 16 / 9S / 21E		Footages: 1,261.00' FSL 1,248.00' FWL		

## Wellbore: NBU 921-16MT

MTD 10,310	TVD 10,304	PBMD 10,256	PBTVD
---------------	---------------	----------------	-------

EVENT INFORMATION:	EVENT ACTIVITY: DRILLING	START DATE: 8/11/2008	AFE NO.: 2007722
	OBJECTIVE: DEVELOPMENT	END DATE: 10/21/2008	
	OBJECTIVE 2: VERTICAL WELL	DATE WELL STARTED PROD.: 8/12/2008	
	REASON: DRILL PROD HOLE	Event End Status: COMPLETE	

RIG OPERATIONS:	Begin Mobilization	Rig On Location	Rig Charges	Rig Operation Start	Finish Drilling	Rig Release	Rig Off Location
PETE MARTIN DRILLING / UI	08/11/2008	08/11/2008	08/11/2008	08/11/2008	08/11/2008	08/11/2008	08/11/2008

Date	Time Start-End	Duration (hr)	Phase	Code	Subco de	P/U	Operation
8/11/2008	SUPERVISOR: LEW WELDON						
	10:00 - 17:00	7.00	DRLCON	02		P	MOVE IN AND RIG UP BUCKET RIG SPUD WELL @ 1000 HR 8/11/08 DRILL AND SET 40' OF SCHEDULE 10 PIPE DRILL RODENT HOLES FOR RIG 41 BLM AND STATE NOTFIED OF SPUD
8/12/2008	SUPERVISOR: LEW WELDON						
	16:00 - 0:00	8.00	DRLSUR	02		P	MOVE IN AND RIG UP AIR RIG SPUD WELL @ 1600 HR 8/12/08 DA AT REPORT TIME 720' DA
8/13/2008	SUPERVISOR: LEW WELDON						
	0:00 - 12:00	12.00	DRLSUR	02		P	RIG DRILLING AHEAD NO WATER 1150'
	12:00 - 0:00	12.00	DRLSUR	02		P	RIG DRILLING AHEAD NO WATER 1500'
8/14/2008	SUPERVISOR: LEW WELDON						
	0:00 - 12:00	12.00	DRLSUR	02		P	RIG DRILLING AHEAD NO WATER 1770' RUN SURVEY .75 DEG.
	12:00 - 0:00	12.00	DRLSUR	02		P	RIG DRILLING AHEAD NO WATER 2070'
8/15/2008	SUPERVISOR: LEW WELDON						
	0:00 - 12:00	12.00	DRLSUR	02		P	RIG DRILLING AHEAD NO WATER 2450'
	12:00 - 0:00	12.00	DRLSUR	02		P	RIG T/D @ 2760' CONDITION HOLE 1 HR RUN SURVEY 3 DEG.
8/16/2008	SUPERVISOR: LEW WELDON						
	0:00 - 5:00	5.00	DRLSUR	05		P	TRIP DP OUT OF HOLE



	5:00 - 10:00	5.00	DRLSUR	11		P	RUN 2724' OF 9 5/8 CSG AND 200' OF 1" PIPE RIG DOWN AIR RIG
	10:00 - 11:00	1.00	DRLSUR	15		P	CEMENT 1ST STAGE WITH 250 SKS LEAD @ 11# 3.82 23 GAL/SK AND 200 SKS TAIL @ 15.8# 1.15 5.0 GAL/SK GOOD RETURNS THRUOUT JOB + - 17 BBL LEAD CMT TO PIT
	11:00 - 11:30	0.50	DRLSUR	15		P	1ST TOP JOB 125 SKS DOWN 1" PIPE GOOD CMT TO SURFACE AND FELL BACK WOC
	11:30 - 13:00	1.50	DRLSUR	15		P	2ND TOP JOB 85 SKS DOWN BS GOOD CMT TO SURFACE AND STAYED AT SURFACE
	13:00 - 13:00	0.00	DRLSUR				NO VISIBLE LEAKS PIT 1/4 FULL WORT
10/7/2008	SUPERVISOR: RON SJOSTROM						
	6:00 - 18:00	12.00	DRLPRO	01	E	P	RIGGING DOWN, LOWER DERRICK @ 15:30, MOVE OUT FRONT END EQUIPMENT, SET UP RIG CAMP ON NEW LOCATION, TRANSFER 800 BBL LIQUID MUD TO NEW LOCATION. 5% MOVED, 75% RIGGED DOWN, 60 MAN HOURS TODAY, 2 BED TRUCKS
	18:00 - 0:00	6.00	DRLPRO	12	D	P	RIG IDLE, SHUT DOWN FOR NIGHT
10/8/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 6:00	6.00	DRLPRO	12	D	P	WAIT ON DAYLIGHT FOR MOVE
	6:00 - 13:30	7.50	DRLPRO	01	E	P	CRANE ON LOCATION 0700 HRS, 3 HAUL TRUCKS, 5 BED TRUCKS, 1 FORKLIFT ARRIVED 0700 HRS, REMOVE DERRICK FROM FLOOR @ 1100 HRS, SET OFF DRAWWORKS, SPLIT SUB, MOVE OFF PUMPS, LIGHT PLANT, WATER TANK, FUEL TANK, LOCATION CLEARED 1330 HRS
	13:30 - 0:00	10.50	DRLPRO	01	B	P	SET MATS, STACK SUB, DERRICK ON FLOOR 1800 HRS, ON STAND 2000 HRS, SET IN RIG EQUIPMENT, RIG UP AIR-WATER-ELECTRIC LINES, BACK YARD EQUIPMENT. LAST TRUCKS LEFT 2030 HRS, CRANE LEFT 2030 HRS, ==100% MOVED, 60% RIGGED UP
10/9/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 14:00	14.00	DRLPRO	01	B	P	RIG UP BACK YARD, RAISE DERRICK @ 0800, RIG UP FLOOR EQUIPMENT, RIG ACCEPTED ON DAYWORK 1400 HRS 10/9/08 MAN HOURS TODAY 70, 356.5 TOTAL FOR MOVE
	14:00 - 18:00	4.00	DRLPRO	13	A	P	NIPPLE UP BOP EQUIPMENT
	18:00 - 22:00	4.00	DRLPRO	13	C	P	TEST BOP EQUIPMENT & CASING
	22:00 - 0:00	2.00	DRLPRO	05	A	P	INSTALL WEAR BUSHING, R/U PICKUP MACHINE, M/U BIT #1, P/U DRILLSTRING & RIH

	22:00 - 0:00	2.00	DRLPRO	05	A	P	INSTALL WEAR BUSHING, R/U PICKUP MACHINE, M/U BIT #1, P/U DRILLSTRING & RIH
10/10/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 6:00	6.00	DRLPRO	05	A	P	P/U DRILLSTRING & RIH, TAG CEMENT @ 2627, R/D TESCO PICKUP MACHINE
	6:00 - 10:00	4.00	DRLPRO	02	F	P	DRILL CEMENT, FE & SHOE TO 12-1/4 HOLE@2778
	10:00 - 14:30	4.50	DRLPRO	02	B	P	SPUD IN AND DRILL 2778-3037, 259' = 57.5 FPH, MW 9.0#
	14:30 - 15:00	0.50	DRLPRO	06	A	P	RIG SERVICE
	15:00 - 15:30	0.50	DRLPRO	09	B	P	WIRELINE SURVEY @ 2957 = 2.0 DEG 149.2 AZ
	15:30 - 0:00	8.50	DRLPRO	02	B	P	DRILL 3037-3512 = 56.5 FPH, MW 9.4#
10/11/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 9:00	9.00	DRLPRO	02	B	P	DRILLING 3512-4017 = 505' = 56.1 FPH, MW 9.4
	9:00 - 9:30	0.50	DRLPRO	09	B	P	WIRELINE SURVEY @ 3938 = 2.0 DEG, 171.4 AZ
	9:30 - 16:00	6.50	DRLPRO	02	B	P	DRILLING 4017-4480 = 463' = 71.2 FPH, MW 9.8##
	16:00 - 16:30	0.50	DRLPRO	06	A	P	RIG SERVICE
	16:30 - 0:00	7.50	DRLPRO	02	B	P	DRILLING 4480-4961 = 481' = 64.1 FPH, MW 10.0#, INC MW DUE TO POPPING SHALES
10/12/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 1:00	1.00	DRLPRO	02	B	P	DRILL 4961-5021 = 60', MW 10.0#
	1:00 - 1:30	0.50	DRLPRO	04	G	P	CIRC PRIOR TO SURVEY
	1:30 - 2:00	0.50	DRLPRO	09	B	P	WIRELINE SURVEY @ 4961 = 2.0 DEG / 184.9 AZ
	2:00 - 16:30	14.50	DRLPRO	02	B	P	DRILLING 5021-5821 = 800' = 55.2 FPH, MW 10.0#
	16:30 - 17:00	0.50	DRLPRO	06	A	P	RIG SERVICE
	17:00 - 20:30	3.50	DRLPRO	02	B	P	DRILL 5821-6011 = 190' = 54.3 FPH, MW 10.2#
	20:30 - 21:00	0.50	DRLPRO	04	G	P	CIRCULATE PRIOR TO SURVEY

	20:30 - 21:00	0.50	DRLPRO	04	G	P	CIRCULATE PRIOR TO SURVEY
	21:00 - 21:30	0.50	DRLPRO	09	B	P	WIRELINE SURVEY @ 5931 = 2.4 DEG, 164.1 AZ
	21:30 - 0:00	2.50	DRLPRO	02	B	P	DRILL 6011-6137 = 126' = 50.4 FPH, MW 10.2#
10/13/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 15:00	15.00	DRLPRO	02	B	P	DRILLING 6137-6801 = 664 = 44.3 FPH, MW 10.4#
	15:00 - 15:30	0.50	DRLPRO	06	A	P	RIG SERVICE
	15:30 - 21:00	5.50	DRLPRO	02	B	P	DRILLING 6801-7023 = 222' = 40.36 FPH, MW 10.5#
	21:00 - 21:30	0.50	DRLPRO	04	G	P	CCH PRIOR TO SURVEY
	21:30 - 22:00	0.50	DRLPRO	09	B	P	WIRELINE SURVEY @ 6943 = 1.8 DEG, 148.0 AZ
	22:00 - 0:00	2.00	DRLPRO	02	B	P	DRILLING 7023-7100 = 77' = 38.5 FPH, MW 10.7#
10/14/2008	SUPERVISOR: RON SJOSTROM						
	0:00 - 14:30	14.50	DRLPRO	02	B	P	DRILLING 7100-7466 = 366 = 25.2 FPH, MW 10.7#
	14:30 - 15:00	0.50	DRLPRO	06	A	P	RIG SERVICE
	15:00 - 15:30	0.50	DRLPRO	04	C	P	CIRCULATE PRIOR TO TRIP OUT
	15:30 - 19:00	3.50	DRLPRO	05	A	P	POOH BIT #1, L/D MONEL, IBS'S, JARS, CHANGE MUD MOTORS, WORK THROUGH TIGHT SPOT 5730
	19:00 - 22:30	3.50	DRLPRO	05	A	P	M/U BIT #2, P/U MUD MOTOR, TRIP IN HOLE GOOD
	22:30 - 23:30	1.00	DRLPRO	03	E	P	WASH & REAM 110' TO TD 7466
	23:30 - 0:00	0.50	DRLPRO	02	B	P	DRILLING 7466-7489 = 23' = 46 FPH, MW 10.8#
10/15/2008	SUPERVISOR: JIM MURRAY						
	0:00 - 7:00	7.00	DRLPRO	02	B	P	DRILLING 7489-7806=317=45.2 MW 11.0
	7:00 - 7:30	0.50	DRLPRO	06	A	P	RIG SERVICE
	7:30 - 0:00	16.50	DRLPRO	02	B	P	DRILLING 7806-8500=694=42.0 MW 11.3

	7:30 - 0:00	16.50	DRLPRO	02	B	P	DRILLING 7806-8500=694=42.0 MW 11.3
10/16/2008	<u>SUPERVISOR:</u> JIM MURRAY						
	0:00 - 14:30	14.50	DRLPRO	02	B	P	DRILLING 8500-9071=571=39.3 11.6
	14:30 - 15:00	0.50	DRLPRO	06	A	P	RIG SERVICE
	15:00 - 0:00	9.00	DRLPRO	02	B	P	DRILLING 9071-9325=254=28.2 11.8
10/17/2008	<u>SUPERVISOR:</u> JIM MURRAY						
	0:00 - 3:00	3.00	DRLPRO	04	B	P	CCH,RAISE MUD WT 11.8 - 12.0 # TO CONTROL GAS FOR BIT TRIP
	3:00 - 7:30	4.50	DRLPRO	05	A	P	PUMP SLUG DROP SURVEY,TOH TIGHT @ 5030' BREAK BIT LD M MTR
	7:30 - 9:30	2.00	DRLPRO	05	A	P	PU M MTR MAKE UP BIT TIH TO SCG SHOE BREAK CIRC
	9:30 - 11:30	2.00	DRLPRO	06	D	P	CUT DRILL LINE
	11:30 - 14:00	2.50	DRLPRO	05	A	P	TIH, BREAK CIRC @ 6500',CIH WASH TO BTM
	14:00 - 16:00	2.00	DRLPRO	02	B	P	DRILLING 9325-9389=64=32 M W 12.1
	16:00 - 16:30	0.50	DRLPRO	06	A	P	RIG SERVICE
	16:30 - 0:00	7.50	DRLPRO	02	A	P	DRILLING 9389-9665=340=35.8 12.2
10/18/2008	<u>SUPERVISOR:</u> JIM MURRAY						
	0:00 - 10:30	10.50	DRLPRO	02	B	P	DRILLING 9665-9887=222=21.1 12.2
	10:30 - 11:30	1.00	DRLPRO	04	C	P	CBU,MIX & PUMP SLUG,DROP SURVEY
	11:30 - 15:30	4.00	DRLPRO	05	A	P	TOH,CHANGE OUT M MTRS & BIT
	15:30 - 16:00	0.50	DRLPRO	06	A	P	RIG SERVICE
	16:00 - 19:30	3.50	DRLPRO	05	A	P	TIH ,BREAK CIRC @ 2800' CIH, BREAK CIRC @ 6500', CIH
	19:30 - 20:00	0.50	DRLPRO	03	E	P	W & R 45' TO BTM

20:00 - 0:00      4.00      DRLPRO      02      B      P      DRILLING 9887-9975=88=22 MW 12.2

10/19/2008      SUPERVISOR: JIM MURRAY

0:00 - 11:00      11.00      DRLPRO      02      B      P      DRILLING 9975-10250=275=25 MW 12.3

11:00 - 11:30      0.50      DRLPRO      06      A      P      RIG SERVICE

11:30 - 13:00      1.50      DRLPRO      02      B      P      DRILLING 10250-10310=60=40 MW 12.4 TD @ 1300 HRS  
10/19/2008

13:00 - 14:00      1.00      DRLPRO      04      C      P      CCH,F/ WIPER TRIP

14:00 - 15:00      1.00      DRLPRO      05      E      P      10 STD WIPER TRIP TO 9350,HOLE GOOD

15:00 - 17:30      2.50      DRLPRO      04      C      P      CCH, SM RU CASERS TO LDDS

17:30 - 0:00      6.50      DRLPRO      05      B      P      LDDS

10/20/2008      SUPERVISOR: JIM MURRAY

0:00 - 1:30      1.50      DRLPRO      08      D      P      LD BHA,PULL WEAR BUSHING

1:30 - 15:00      13.50      DRLPRO      08      F      P      SM RU HALLIBURTON,HAVING TROUBLE W/ NEUTRON TOOL,  
HAVING TO MAKE 2 RUNS,1ST RUN TRIPLE COMBO W/O  
NEUTRON SOURCE,2ND RUN NEUTRON DENSITY,NGRT,  
LOGGERS TD 10322',RD SAME

15:00 - 22:00      7.00      DRLPRO      08      B      P      SM RU TESCO RUN 244 JTS OF 41/2 P110 11.6# CSG SHOE  
@10,305

22:00 - 23:00      1.00      DRLPRO      04      E      P      CIRC CSG RU HALCO

23:00 - 0:00      1.00      DRLPRO      08      B      P      SM TEST LINES TO 5000,PUMP 10 BBLS WATER,20 BBLS MUD  
FLUSH,10 BBLS WATER,30 BBLS SCAVENGER CMT @ 9,5#,390  
SKS 154 BBLS LEAD @ 12.2#

10/21/2008      SUPERVISOR: JIM MURRAY

0:00 - 1:30      1.50      DRLPRO      15      A      P      PUMP 1370 SKS 309 BBLS TAIL @ 14.3#,DISPLACE W/ 159.9  
BBLS FW, BUMP PLUG W/ 3550 PSI 500 OVER FLOATS  
OK,GOOD CIRC DURING JOB,NO CMT TO SURFACE

1:30 - 2:00      0.50      DRLPRO      11      B      P      LAND CSG W/ 75,000 TEST SEALS TO 5000# LD SETTING TOOL

2:00 - 6:00      4.00      DRLPRO      13      A      P      NDBOP,CLEAN PITS,RELEASE RIG TO NBU 921-18D @ 0600 HRS  
10/21/2008

Wins No.: 94956

NBU 921-16MT

API No.: 4304739362

<b>Wins No.:</b> 94956	<b>NBU 921-16MT</b>	<b>API No.:</b> 4304739362					
<b>EVENT INFORMATION:</b> <div style="display: flex; justify-content: space-between;"> <div> EVENT ACTIVITY: COMPLETION  OBJECTIVE: DEVELOPMENT  OBJECTIVE 2: ORIGINAL  REASON: MV </div> <div> START DATE: 10/30/2008  END DATE: 11/5/2008  DATE WELL STARTED PROD.: 8/12/2008  Event End Status: COMPLETE </div> <div> AFE NO.: 2007722 </div> </div>							
<b>RIG OPERATIONS:</b> <div style="display: flex; justify-content: space-between;"> <div>Begin Mobilization</div> <div>Rig On Location</div> <div>Rig Charges</div> <div>Rig Operation Start</div> <div>Finish Drilling</div> <div>Rig Release</div> <div>Rig Off Location</div> </div>							
KEY 243 / 243      10/30/2008      11/05/2008							
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode	P/U	Operation
10/30/2008	<u>SUPERVISOR:</u> KEN WARREN						
	7:00 - 7:15	0.25	COMP	48		P	HSM, R/D, R/U
	7:15 - 7:15	0.00	COMP	47	B	P	MIRU SPOT EQUIP, N/D WELL HEAD, N/U BOPS, P/U 3-7/8 MILL W/ X-OVER, TALLEY & P/U 297 JNTS 2-3/8 L-80 TBG, EOT @ 9430', POOH W/ TBG & MILL, MIRU B&C QUICK TEST, PRESSURE TEST CSG & FRAC VALVES TO 7500# [GOOD TEST] SWI. 17:00
10/31/2008	<u>SUPERVISOR:</u> KEN WARREN						
	7:00 - 15:00	8.00	COMP	30	C	P	STND BY
11/3/2008	<u>SUPERVISOR:</u> KEN WARREN						
	7:00 - 7:15	0.25	COMP	48		P	HSM, SPOTTING EQUIP ON LOC
	7:15 - 10:00	2.75	COMP	46	E	Z	WAITING TO SPOT WEATHERFORD EQUIP.
	10:00 - 17:00	7.00	COMP	36	E	P	MIRU CUTTERS WIRELINE, STG #1] P/U RIH W/ 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90° PH, 10160'-10166' 24 HOLES, 10122'-10126' 167 HOLES, [40 HOLES]
WHP=0#, BRK DN PERFS @ 4078#, INJT PSI=4700#, INJT RT=51, ISIP=3256#, FG=.76, PUMP'D 4606 BBLS SLK WTR W/ 160734# 30/50 MESH, W/ 5000# RESIN COAT IN TAIL, ISIP=3224#, FG=.76, AR=53.8, AP=4952, MR=56.3, MP=6114, NPI=-32#, 40/40 CALC PERFS OPEN 100%. SWIFN.							
11/4/2008	<u>SUPERVISOR:</u> KEN WARREN						
	7:00 - 7:15	0.25	COMP	48		P	HSM, WORKING W/ WIRE LINE
	7:15 - 17:00	9.75	COMP	36	E	P	OPEN WELL 1800# SICP, STG #2] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 9978', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90° PH. 9942'-9948' 24 HOLES. [ TOP 2' GUN SHOT OUT OF ZONE PUTTING 8 HOLES 9938'-9940' WAIT ON NEW GUNS TO BE REBUILT & BROUGHT OUT. FINISH SHOOTING STG #2, 9904'-9906' 8 HOLES, 9854'-9856' 8 HOLES, [48 HOLES TOTAL]
WHP=0#, BRK DN PERFS @ 4264#, INJT PSI=4900#, INJT RT=52.9, ISIP=3130#, FG=.76, PUMP'D 2684.1 BBLS SLK WTR W/ 97706# 30/50 MESH W/ 5000# RESIN COAT IN TAIL, ISIP=3247#, FG=.77, AR=52.8, AP=4968#, MR=53.1, MP=6606, NPI=117#, 48/48 CALC PERFS OPEN.							
STG #3] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 9716', PER MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90° PH, [40 HOLES] 9682'-9686' 16 HOLES, 9562'-9566' 16 HOLES, 9504'-9506' 8 HOLES.							
WHP=0#, BRK DN PERFS @ 3873#, INJT PSI=5100#, INJT RT=50, ISIP=2521#, FG=.70, PUMP'D 2685.2 BBLS SLK WTR W/ 97691# 30/50 MESH W/ 5000# RESIN COAT IN TAIL, ISIP=2966#, FG=.75, AR=48.7, AP=4508#, MR=50.4, MP=6108#, NPI=445#, 27/40 67% CALC PERFS OPEN.							
STG #4] P/U RIH W/ BKR 8K CBP & PERF GUN. SET CBP @ 9466', PERF MESAVERDE USING 3-3/8 EXPEND, 23 GRM, 0.36" HOLE, 4 SPF, 90° PH [40 HOLES] 9432'-9436' 16 HOLES, 9400'-9404' 16 HOLES, 9342'-9344' 8 HOLES.							
WHP=2300#, BRK DN PERFS @ 7562#, INJT PSI=5050#, INJT RT=50.3, ISIP=2958#, FG=.76, PUMP'D 43338.7 BBLS SLK WTR W/ 5000# RESIN COAT IN TAIL, ISIP=3003#, FG=.76, AR=49.8, AP=4744#, MR=50.6, MP=7562#, NPI=45#, 34/40 CALC PERFS OPEN 83%							
P/U RIH W/ BKR 8K CBP & SET @ 9292', R/D CUTTERS WIRE LINE & WEATHERFORD FRAC CREW, SWIFN.							

11/5/2008 SUPERVISOR: KEN WARREN

7:00 - 7:15 0.25 COMP 48 P

7:15 - 17:00 9.75 COMP 44 C P

HSM, MAKING CONNECTIONS

OPEN WEL 0# CSG, N/D FRAC VALVES, N/U BOPS, R/U TBG EQUIP, P/U 3-7/8 BIT W/ POBS PKG, RIH W/ 2-3/8 TBG TAG KILL PLUG @ 9298' P/U PWR SWVL.

PLUG #1] EST CIRC W/ RIG PUMP, DRL THROUGH BKR 8K CBP @ 9298' IN 10 MIN. 1200# INCREASE.

PLUG #2] CONTINUE TO RIH TAG SAND @ 9436' C/O & DRL THROUGH BKR 8K CBP @ 9466' IN 10 MIN. 0# INCREASE.

PLUG #3] CONTINUE TO RIH TAG SAND @ 9686' C/O & DRL THROUGH BKR 8K CBP @ 9716' IN 10 MIN. 1600# INCREASE.

PLUG #4] CONTINUE TO RIH TAG SAND @ 9948' C/O & DRL THROUGH BKR 8K CBP @ 9978' IN 10 MIN. 1600# INCREASE. CONTINUE TO RIH C/O TO PBTD @ 10,256' CIRC HOLE, R/D PWR SWVL, L/D 13 JNTS TBG, P/U HANGER LAND W/ 309 JNTS 2-3/8 L-80 TBG EOT @ 9822.41' DROP BALL, R/D TBG EQUIP, N/D BOPS, N/U WELL HEAD, PUMP OFF BIT W/ 1/2 BBL, @ 3200#, TURN WELL OVER TO FLOW BACK CREW.

## TBG DETAIL

KB 17.00

HANGER .83

309 JNTS 2-3/8 L-80 9801.38

X-NIPPLE [1.875] 3.20

11/6/2008 SUPERVISOR: RYAN THOMAS

7:00 - 33 A

7 AM FLBK REPORT: CP 2300#, TP 2000#, 16/64" CK, 65 BWPH, TRACE SAND, - GAS  
TTL BBLS RECOVERED: 3570  
BBLS LEFT TO RECOVER: 10744

11/7/2008 SUPERVISOR: DOYLE HOLMES

7:00 - 33 A

7 AM FLBK REPORT: CP 1900#, TP 2000#, 16/64" CK, 60 BWPH, TRACE SAND, - GAS  
TTL BBLS RECOVERED: 5010  
BBLS LEFT TO RECOVER: 9304

11/8/2008 SUPERVISOR: DOYLE HOLMES

7:00 - 33 A

7 AM FLBK REPORT: CP 2200#, TP 2100#, 16/64" CK, 45 BWPH, TRACE SAND, - GAS  
TTL BBLS RECOVERED: 6240  
BBLS LEFT TO RECOVER: 8074

11/9/2008 SUPERVISOR: DOYLE HOLMES

7:00 - 33 A

7 AM FLBK REPORT: CP 3200#, TP 2300#, 18/64" CK, 38 BWPH, TRACE SAND, - GAS  
TTL BBLS RECOVERED: 7355  
BBLS LEFT TO RECOVER: 6959

10:30 - PROD

WELL TURNED TO SALES @ 1030 HR ON 11/09/2008 - FTP 2100#, CP 2300#, CK 16/64", 700 MCFD, 1080 BWPD

11/10/2008 SUPERVISOR: DOYLE HOLMES

7:00 - 33 A

7 AM FLBK REPORT: CP 3500#, TP 2300#, 18/64" CK, 29 BWPH, TRACE SAND, - GAS  
TTL BBLS RECOVERED: 8192  
BBLS LEFT TO RECOVER: 6122



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		6. LEASE DESIGNATION AND SERIAL NUMBER: UT ST ML-3141-A
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME TRIBAL SURFACE
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		7. UNIT or CA AGREEMENT NAME UNIT #891008900A
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078		8. WELL NAME and NUMBER: NBU 921-16MT
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1261'FSL, 1248'FWL  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:		9. API NUMBER: 4304739362
PHONE NUMBER: (435) 781-7024		10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S, 21E		12. COUNTY UINTAH
		13. STATE UTAH

14. DATE SPUNDED: 8/11/2008	15. DATE T.D. REACHED: 10/19/2008	16. DATE COMPLETED: 11/19/2008	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 4823'GL
18. TOTAL DEPTH: MD 10,310 TVD	19. PLUG BACK T.D.: MD 10,256 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL-CCL-GR, SD, DSN, ACTR			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,760		660			
7 7/8"	4 1/2 I-80	11.6#		10,310		1760			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	9,822							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) MESAVERDE	9,342	10,166			9,342 10,166	0.36	149	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) WSMVD								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
9342'-10,166'	PMP 14,314 BBLs SLICK H2O & 522,770# 30/50 OTTOWA SD

29. ENCLOSED ATTACHMENTS:

- |   |  |                                       |   |
|---|--|---------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS                         | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT   | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS   | <input type="checkbox"/> OTHER: _____ |   |

30. WELL STATUS:

PROD

RECEIVED

DEC 18 2003

DIV. OF OIL, GAS & MINING

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in Item #26)

DATE FIRST PRODUCED: 11/19/2008	TEST DATE: 11/13/2008	HOURS TESTED: 12	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 1,930	WATER – BBL: 300	PROD. METHOD: FLOWING
CHOKE SIZE: 18/64	TBG. PRESS. 719	CSG. PRESS. 2,843	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

## INTERVAL B (As shown in Item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL C (As shown in Item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL D (As shown in Item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	1,674				
MAHOGANY	2,496				
WASATCH	5,100	8,048			
MESAVERDE	8,064	10,309			

## 35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 12/12/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

RECEIVED  
DEC 18 2008

DIV. OF OIL, GAS &amp; MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTSTML-3141-A
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: TRIBAL SURFACE
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 921-16MT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1261'FSL, 1248'FWL COUNTY: UINTAH		9. API NUMBER: 4304739362
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S, 21E STATE: UTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input checked="" type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION TO RECOMPLETE THE SUBJECT WELL LOCATION. THE OPERATOR PROPOSES TO COMPLETE THE WASATCH AND MESAVERDE FORMATIONS. THE OPERATOR REQUESTS AUTHORIZATION TO COMMINGLE THE NEWLY WASATCH AND MESAVERDE FORMATIONS.

PLEASE REFER TO THE ATTACHED RECOMPLETION PROCEDURE.

COPY SENT TO OPERATOR

Date: 3-4-2009

Initials: KS

RECEIVED

FEB 23 2009

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO TITLE REGULATORY ANALYST  
SIGNATURE [Signature] DATE 2/20/2009

(This space for State use only)

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING  
DATE: 2/26/09  
BY: [Signature]  
(See Instructions on Reverse Side)  
+ Case 173-14

**Name:** NBU 921-16MT  
**Location:** SWSW Sec. 16 T9S R21E  
**Uintah County, UT**  
**Date:** 2/13/09

**ELEVATIONS:** 4840 GL 4823 KB

**TOTAL DEPTH:** 10310 **PBTD:** 10256  
**SURFACE CASING:** 9 5/8", 36# J-55 ST&C @ 2745'  
**PRODUCTION CASING:** 4 1/2", 11.6#, I-80 LT&C @ 10306'  
Marker Joint **5063' - 5084'**

**TUBULAR PROPERTIES:**

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

**TOPS:**

1674' Green River  
1986' Birds Nest  
2496' Mahogany  
5100' Wasatch  
8064' Mesaverde

CBL indicates good cement below 1500'

**GENERAL:**

- A minimum of **20** tanks (cleaned lined 500 bbl) of recycled water will be required. Note: Use biocide in tanks and the water needs to be at least 45°F at pump time.
- All perforation depths are from Halliburtons Induction-Density-Neutron log dated 10/20/2008
- **6** fracturing stages required for coverage.
- Procedure calls for 7 CBP's (**8000** psi).
- Calculate open perforations after each breakdown. If less than 60% of the perforations appear to be open, ball out with 15% HCl.
- Put scale inhibitor 3 gals/1000 gals (in pad and 1/2 the ramp) and 10 gals/1000 gals in all flushes except the final stage. Remember to pre-load the casing with scale inhibitor for the very first stage with 10 gpt.
- 30/50 mesh Ottawa sand, **Slickwater frac.**
- Maximum surface pressure **6200** psi.
- Flush volumes are the sum of slick water and acid used during displacement (include scale inhibitor as mentioned above). **DO NOT OVERDISPLACE.** Stage acid and scale inhibitor if necessary to cover the next perforated interval.

- Service companies need to provide surface/production annulus pop-offs to be set for 1500 psi for each frac.
- Pump 20/40mesh **resin coated sand** last 5,000# of all frac stages
- Tubing Currently Landed @~9823
- Originally completed on 11/3/08

#### **Existing Perforations:**

##### **PERFORATIONS**

<b>Formation (Bench)</b>	<b>Top</b>	<b>Btm</b>	<b>spf</b>	<b>Shots</b>	<b>Date</b>
MESA VERDE	9342	9344	4	8	11/03/2008
MESA VERDE	9400	9404	4	16	11/03/2008
MESA VERDE	9432	9436	4	16	11/03/2008
MESA VERDE	9504	9506	4	8	11/03/2008
MESA VERDE	9562	9566	4	16	11/03/2008
MESA VERDE	9682	9686	4	16	11/03/2008
MESA VERDE	9854	9856	4	8	11/03/2008
MESA VERDE	9904	9906	4	8	11/03/2008
MESA VERDE	9938	9940	4	8	11/03/2008
MESA VERDE	9942	9948	4	24	11/03/2008
MESA VERDE	10122	10126	4	16	11/03/2008
MESA VERDE	10160	10166	4	24	11/03/2008

#### **PROCEDURE:**

1. MIRU. Control well with recycled water and biocide as required. ND WH, NU BOP's and test.
2. TOO H with 2-3/8", 4.7#, J-55 (or N-80) tubing (currently landed at ~9823'). Visually inspect for scale and consider replacing if needed.
3. If tbg looks ok consider running a gauge ring to 9330 (50' below proposed CBP). Otherwise P/U a mill and C/O to 9330 (50' below proposed CBP).
4. Set 8000 psi CBP at ~9280'. Pressure test BOP and casing to 6000 psi. .
5. Perf the following with 3-3/8" gun, 23 gm, 0.36"hole:
 

Zone	From	To	spf	# of shots
MESAVERDE	9067	9072	3	15
MESAVERDE	9120	9122	3	6
MESAVERDE	9186	9188	3	6
MESAVERDE	9246	9250	3	12
6. Breakdown perfs and establish injection rate (include scale inhibitor in fluid). Spot 250 gal of 15% HCl and let soak. Fracture as outlined in Stage 1 on attached listing. Under-displace to ~9017' and trickle 250gal 15%HCL w/ scale inhibitor in flush .
7. Set 8000 psi CBP at ~8870'. Perf the following 3-3/8" gun, 23 gm, 0.36"hole:
 

Zone	From	To	spf	# of shots
MESAVERDE	8752	8756	3	12

MESAVERDE	8786	8790	3	12
MESAVERDE	8834	8840	3	18

8. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 2 on attached listing. Under-displace to ~8712' and trickle 250gal 15%HCL w/ scale inhibitor in flush. Note: TIGHT SPACING

9. Set 8000 psi CBP at ~8702'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
MESAVERDE	8530	8534	4	16
MESAVERDE	8562	8564	4	8
MESAVERDE	8594	8596	3	6
MESAVERDE	8668	8672	3	12

10. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 3 on attached listing. Under-displace to ~8502' trickle 250gal 15%HCL w/ scale inhibitor in flush. Note: TIGHT SPACING

11. Set 8000 psi CBP at ~8492'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
MESAVERDE	8288	8290	3	6
MESAVERDE	8352	8356	3	12
MESAVERDE	8410	8414	4	16
MESAVERDE	8460	8462	3	6

12. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 4 on attached listing. Under-displace to ~8238' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

13. Set 8000 psi CBP at ~8150'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	7996	8002	3	18
WASATCH	8030	8032	3	6
MESAVERDE	8114	8120	3	18

14. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 5 on attached listing. Under-displace to ~7946' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

15. Set 8000 psi CBP at ~7236'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6996	6999	3	9
WASATCH	7076	7080	4	16
WASATCH	7166	7170	3	12
WASATCH	7204	7206	3	6

16. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 6 on attached listing. Under-displace to ~6946' and flush only with recycled water.

17. Set 8000 psi CBP at ~6946'.

18. TIH with 3 7/8" mill, pump off sub, SN and tubing.
19. Mill ALL plugs and clean out to PBTD at 10256. Land tubing at  $\pm 9874'$  pump off bit and bit sub. This well WILL be commingled at this time.
20. Clean out well with foam and/or swabbing unit until steady flow has been established from recomplete.
21. RDMO

**For design questions, please call  
Conner Staley, Denver, CO  
(720)-929-6419 (Office)**

**For field implementation questions, please call  
Robert Miller, Vernal, UT  
4350781 7041 (Office)**

NOTES:  
Tight Spacing on stages 2,3

Fracturing Schedules  
Name: NBU 921-16MT  
Slickwater Frac

Stage	Zone	Perfs		SPF	Holes	Rate BPM	Fluid Type	Initial ppg	Final ppg	Fluid	Volume gals	Cum Vol gals	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CBP to Flush	Scale Inhib., gal.
		Top, ft.	Bot, ft.																	
1	MESAVERDE	9067	9072	3	15	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	no perfs					0 ISIP and 5 min ISIP													58
	MESAVERDE	9120	9122	3	6	50	Slickwater Pad			Slickwater	13,061	13,061	311	311	15.0%	0.0%	0	0		39
	MESAVERDE	9186	9188	3	6	50	Slickwater Ramp	0.25	1	Slickwater	24,671	37,733	587	898	28.3%	16.7%	15,420	15,420		37
	MESAVERDE	9246	9250	3	12	50	SW Sweep	0	0	Slickwater	0	37,733	0	898	0.0%	0.0%	0	15,420		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	24,671	62,404	587	1,486	28.3%	33.4%	30,839	46,259		37
	MESAVERDE					50	SW Sweep	0	0	Slickwater	5,250	67,654	125	1,611	0.0%	0.0%	0	46,259		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	3,000	70,654	71	1,682	3.2%	3.0%	3,000	49,259		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	24,671	92,325	587	2,198	28.3%	45.7%	43,175	92,433		0
	MESAVERDE					50	Flush (4-1/2")				5,886	98,211	140	2,338				92,433		58
	MESAVERDE						ISDP and 5 min ISDP					98,211								229
		# of Perfs/stage			39												50,626	53,740	lbs sand/ft	
						46.8	<< Above pump time (min)										gal/ft	CBP depth	147	
2	MESAVERDE	8752	8756	3	12	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	8786	8790	3	12	0	ISIP and 5 min ISIP													
	MESAVERDE	8834	8840	3	18	50	Slickwater Pad			Slickwater	8,049	8,049	192	192	15.0%	0.0%	0	0		24
	MESAVERDE					50	Slickwater Ramp	0.25	1	Slickwater	15,204	23,254	362	554	28.3%	17.2%	9,503	9,503		23
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	23,254	0	554	0.0%	0.0%	0	9,503		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	15,204	38,458	362	916	28.3%	34.5%	19,005	28,508		23
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	38,458	0	916	0.0%	0.0%	0	28,508		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	38,458	0	916	0.0%	0.0%	0	28,508		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	15,204	53,663	362	1,278	28.3%	48.3%	26,608	55,116		0
	MESAVERDE					50	Flush (4-1/2")				5,887	59,350	135	1,413				55,116		57
	MESAVERDE						ISDP and 5 min ISDP					59,350								126
		# of Perfs/stage			42												50,626	51,996	lbs sand/ft	
						25.8	<< Above pump time (min)										gal/ft	CBP depth	8,702	
3	MESAVERDE	8530	8534	4	16	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	8562	8564	4	8	0	ISIP and 5 min ISIP													
	MESAVERDE	8594	8596	3	6	50	Slickwater Pad			Slickwater	8,880	8,880	211	211	15.0%	0.0%	0	0		27
	MESAVERDE	8668	8672	3	12	50	Slickwater Ramp	0.25	1	Slickwater	16,773	25,653	399	611	28.3%	17.2%	10,483	10,483		25
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	25,653	0	611	0.0%	0.0%	0	10,483		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	16,773	42,427	399	1,010	28.3%	34.5%	20,967	31,450		25
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	42,427	0	1,010	0.0%	0.0%	0	31,450		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	42,427	0	1,010	0.0%	0.0%	0	31,450		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	16,773	59,200	399	1,410	28.3%	48.3%	29,353	60,803		0
	MESAVERDE					50	Flush (4-1/2")				5,550	64,750	132	1,542				60,803		55
	MESAVERDE						ISDP and 5 min ISDP					64,750								132
		# of Perfs/stage			42												80,000	82,167	lbs sand/ft	
						28.2	<< Above pump time (min)										gal/ft	CBP depth	8,492	
4	MESAVERDE	8288	8290	3	6	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	8352	8356	3	12	0	ISIP and 5 min ISIP													
	MESAVERDE	no perfs																		
	MESAVERDE	8410	8414	4	16	50	Slickwater Ramp	0.25	1	Slickwater	17,227	26,347	410	627	28.3%	17.2%	10,767	10,767		26
	MESAVERDE	8450	8452	3	6	50	SW Sweep	0	0	Slickwater	0	26,347	0	627	0.0%	0.0%	0	10,767		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	17,227	43,573	410	1,037	28.3%	34.5%	21,533	32,300		26
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	43,573	0	1,037	0.0%	0.0%	0	32,300		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	43,573	0	1,037	0.0%	0.0%	0	32,300		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	17,227	60,800	410	1,448	28.3%	48.3%	30,147	62,447		0
	MESAVERDE					50	Flush (4-1/2")				5,378	66,178	128	1,576				62,447		53
	MESAVERDE						ISDP and 5 min ISDP					66,178								132
		# of Perfs/stage			40												80,000	82,167	lbs sand/ft	
						29.0	<< Above pump time (min)										gal/ft	CBP depth	8,150	
5	WASATCH	7996	8002	3	18	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	8030	8032	3	6	0	ISIP and 5 min ISIP													
	MESAVERDE	8114	8120	3	18	50	Slickwater Pad			Slickwater	5,809	5,809	138	138	15.0%	0.0%	0	0		17
	MESAVERDE					50	Slickwater Ramp	0.25	1	Slickwater	10,973	16,782	261	400	28.3%	17.2%	6,858	6,858		16
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	16,782	0	400	0.0%	0.0%	0	6,858		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	10,973	27,755	261	661	28.3%	34.5%	13,716	20,574		16
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	27,755	0	661	0.0%	0.0%	0	20,574		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	27,755	0	661	0.0%	0.0%	0	20,574		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	10,973	38,727	261	922	28.3%	48.3%	19,202	39,776		0
	MESAVERDE					50	Flush (4-1/2")				5,187	43,915	124	1,046				39,776		47
	MESAVERDE						ISDP and 5 min ISDP					43,915								97
		# of Perfs/stage			42												25,312	25,998	lbs sand/ft	
						18.4	<< Above pump time (min)										gal/ft	CBP depth	7,236	
6	WASATCH	6996	6999	3	9	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	7076	7080	4	16	0	ISIP and 5 min ISIP													
	WASATCH	7166	7170	3	12	50	Slickwater Pad			Slickwater	3,645	3,645	87	87	15.0%	0.0%	0	0		11
	WASATCH	7204	7206	3	6	50	Slickwater Ramp	0.25	1	Slickwater	6,885	10,530	164	251	28.3%	17.2%	4,303	4,303		10
	WASATCH					50	SW Sweep	0	0	Slickwater	0	10,530	0	251	0.0%	0.0%	0	4,303		0
	WASATCH					50	Slickwater Ramp	1	1.5	Slickwater	6,885	17,415	164	415	28.3%	34.5%	8,606	12,909		10
	WASATCH					50	SW Sweep	0	0	Slickwater	0	17,415	0	415	0.0%	0.0%	0	12,909		0
	WASATCH					50	Slickwater Ramp	0.5	1.5	Slickwater	0	17,415	0	415	0.0%	0.0%	0	12,909		0
	WASATCH					50	Slickwater Ramp	1.5	2	Slickwater	6,885	24,300	164	579	28.3%	48.3%	12,049	24,958		0
	WASATCH					50	Flush (4-1/2")				4,534	28,834	108	687				24,958		0
	WASATCH						ISDP and 5 min ISDP					28,834								32
		# of Perfs/stage			43												25,312	25,998	lbs sand/ft	
						11.6	<< Above pump time (min)										gal/ft	CBP depth	6,946	
Totals					248						Total Fluid	365,869	gals	8,601	bbls		Total Sand	336,533		LOOK
						2.7						8,473	bbls		19.1	tanks		Total Scale Inhib. =	748	



**Name** NBU 921-16MT  
**Perforation and CBP Summary**

Stage	Zones	Perforations		SPF	Holes	Fracture Coverage		
		Top, ft	Bottom, ft					
1	MESAVERDE	9067	9072	3	15	9048.5	to	9079.5
	MESAVERDE		no perfs			9091.5	to	9101
	MESAVERDE	9120	9122	3	6	9102.5	to	9128.5
	MESAVERDE	9186	9188	3	6	9168.5	to	9191
	MESAVERDE	9246	9250	3	12	9212.5	to	9274.5
	# of Perfs/stage				39	CBP DEPTH	8,870	
2	MESAVERDE	8752	8756	3	12	8743	to	8760.5
	MESAVERDE	8786	8790	3	12	8777	to	8797
	MESAVERDE	8834	8840	3	18	8810.5	to	8843.5
	# of Perfs/stage				42	CBP DEPTH	8,702	
3	MESAVERDE	8530	8534	4	16	8523.5	to	8544.5
	MESAVERDE	8562	8564	4	8	8555	to	8591
	MESAVERDE	8594	8596	3	6	8592.5	to	8601.5
	MESAVERDE	8668	8672	3	12	8657	to	8672.5
	# of Perfs/stage				42	CBP DEPTH	8,492	
4	MESAVERDE	8288	8290	3	6	8285.5	to	8294.5
	MESAVERDE	8352	8356	3	12	8349	to	8361
	MESAVERDE		no perfs			8389.5	to	8395.5
	MESAVERDE	8410	8414	4	16	8399	to	8432.5
	MESAVERDE	8460	8462	3	6	8453	to	8462
	# of Perfs/stage				40	CBP DEPTH	8,150	
5	WASATCH	7996	8002	3	18	7991	to	8006
	WASATCH	8030	8032	3	6	8027.5	to	8032
	MESAVERDE	8114	8120	3	18	8098.5	to	8123
	# of Perfs/stage				42	CBP DEPTH	7,236	
6	WASATCH	6996	6999	3	9	6992.5	to	7007
	WASATCH	7076	7080	4	16	7073.5	to	7090
	WASATCH	7166	7170	3	12	7163.5	to	7175.5
	WASATCH	7204	7206	3	6	7201	to	7209
	# of Perfs/stage				43	CBP DEPTH	6,946	
Totals					248			

Fracturing Schedules  
Name NBU 921-16MT  
Slickwater Frac

Stage	Zone	Perfs		SPF	Holes	Rate BPM	Fluid Type	Initial ppg	Final ppg	Fluid	Volume gals	Cum Vol gals	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CBP to Flush	Scale Inhib., gal.
		Top, ft.	Bot., ft.																	
1	MESAVERDE	9067	9072	3	15	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	no perfs				0	ISIP and 5 min ISIP													58
	MESAVERDE	9120	9122	3	6	50	Slickwater Pad			Slickwater	13,061	13,061	311	311	15.0%	0.0%	0	0		39
	MESAVERDE	9186	9188	3	6	50	Slickwater Ramp	0.25	1	Slickwater	24,671	37,733	587	898	28.3%	16.7%	15,420	15,420		37
	MESAVERDE	9246	9250	3	12	50	SW Sweep	0	0	Slickwater	0	37,733	0	898	28.3%	0.0%	0	15,420		0
	MESAVERDE					50	Slickwater Ramp	0	1.5	Slickwater	24,671	62,404	587	1,486	28.3%	33.4%	30,839	46,259		37
	MESAVERDE					50	SW Sweep	1	0	Slickwater	5,250	67,654	125	1,611	28.3%	0.0%	0	46,259		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	3,000	70,654	71	1,682	28.3%	3.2%	3,000	49,259		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	24,671	92,325	587	2,198	28.3%	46.7%	43,175	92,433		0
	MESAVERDE					50	Flush (4-1/2")				5,886	98,211	140	2,338				92,433		58
	MESAVERDE						ISDP and 5 min ISDP					98,211								229
		# of Perfs/stage			39											gal/ft	50,625	53,740	lbs sand/ft	
						46.8	<< Above pump time (min)										CBP depth	8,870		147
2	MESAVERDE	8752	8756	3	12	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	8786	8790	3	12	0	ISIP and 5 min ISIP													
	MESAVERDE	8834	8840	3	18	50	Slickwater Pad			Slickwater	8,049	8,049	192	192	15.0%	0.0%	0	0		24
	MESAVERDE					50	Slickwater Ramp	0.25	1	Slickwater	15,204	23,254	362	554	28.3%	17.2%	9,503	9,503		23
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	23,254	0	554	28.3%	0.0%	0	9,503		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	15,204	38,458	362	916	28.3%	34.5%	19,005	28,508		23
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	38,458	0	916	28.3%	0.0%	0	28,508		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	38,458	0	916	28.3%	0.0%	0	28,508		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	15,204	53,663	362	1,278	28.3%	48.3%	26,608	55,116		0
	MESAVERDE					50	Flush (4-1/2")				5,687	59,350	135	1,413				55,116		57
	MESAVERDE						ISDP and 5 min ISDP					59,350								126
		# of Perfs/stage			42											gal/ft	50,625	51,996	lbs sand/ft	
						25.6	<< Above pump time (min)										CBP depth	8,702		10
3	MESAVERDE	8530	8534	4	16	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	8562	8564	4	8	0	ISIP and 5 min ISIP													
	MESAVERDE	8594	8596	3	6	50	Slickwater Pad			Slickwater	8,880	8,880	211	211	15.0%	0.0%	0	0		27
	MESAVERDE	8668	8672	3	12	50	Slickwater Ramp	0.25	1	Slickwater	16,773	25,653	399	611	28.3%	17.2%	10,483	10,483		25
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	25,653	0	611	28.3%	0.0%	0	10,483		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	16,773	42,427	399	1,010	28.3%	34.5%	20,967	31,450		25
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	42,427	0	1,010	28.3%	0.0%	0	31,450		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	42,427	0	1,010	28.3%	0.0%	0	31,450		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	16,773	59,200	399	1,410	28.3%	48.3%	29,353	60,803		0
	MESAVERDE					50	Flush (4-1/2")				5,550	64,750	132	1,542				60,803		55
	MESAVERDE						ISDP and 5 min ISDP					64,750								132
		# of Perfs/stage			42											gal/ft	80,000	82,167	lbs sand/ft	
						28.2	<< Above pump time (min)										CBP depth	8,492		10
4	MESAVERDE	8288	8290	3	6	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	8352	8356	3	12	0	ISIP and 5 min ISIP													
	MESAVERDE	no perfs				50	Slickwater Pad			Slickwater	9,120	9,120	217	217	15.0%	0.0%	0	0		27
	MESAVERDE	8410	8414	4	16	50	Slickwater Ramp	0.25	1	Slickwater	17,227	26,347	410	627	28.3%	17.2%	10,767	10,767		26
	MESAVERDE	8460	8462	3	6	50	SW Sweep	0	0	Slickwater	0	26,347	0	627	28.3%	0.0%	0	10,767		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	17,227	43,573	410	1,037	28.3%	34.5%	21,533	32,300		26
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	43,573	0	1,037	28.3%	0.0%	0	32,300		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	43,573	0	1,037	28.3%	0.0%	0	32,300		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	17,227	60,800	410	1,448	28.3%	48.3%	30,147	62,447		0
	MESAVERDE					50	Flush (4-1/2")				5,378	66,178	128	1,576				62,447		53
	MESAVERDE						ISDP and 5 min ISDP					66,178								132
		# of Perfs/stage			40											gal/ft	80,000	82,167	lbs sand/ft	
						29.0	<< Above pump time (min)										CBP depth	8,150		88
5	WASATCH	7996	8002	3	18	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	8030	8032	3	6	0	ISIP and 5 min ISIP													
	MESAVERDE	8114	8120	3	18	50	Slickwater Pad			Slickwater	5,809	5,809	138	138	15.0%	0.0%	0	0		17
	MESAVERDE					50	Slickwater Ramp	0.25	1	Slickwater	10,973	16,782	261	400	28.3%	17.2%	6,858	6,858		16
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	16,782	0	400	28.3%	0.0%	0	6,858		0
	MESAVERDE					50	Slickwater Ramp	1	1.5	Slickwater	10,973	27,755	261	661	28.3%	34.5%	13,716	20,574		16
	MESAVERDE					50	SW Sweep	0	0	Slickwater	0	27,755	0	661	28.3%	0.0%	0	20,574		0
	MESAVERDE					50	Slickwater Ramp	0.5	1.5	Slickwater	0	27,755	0	661	28.3%	0.0%	0	20,574		0
	MESAVERDE					50	Slickwater Ramp	1.5	2	Slickwater	10,973	38,727	261	922	28.3%	48.3%	19,202	39,776		0
	MESAVERDE					50	Flush (4-1/2")				5,187	43,915	124	1,046				39,776		47
	MESAVERDE						ISDP and 5 min ISDP					43,915								97
		# of Perfs/stage			42											gal/ft	25,312	25,998	lbs sand/ft	
						18.4	<< Above pump time (min)										CBP depth	7,236		710
6	WASATCH	6996	6999	3	9	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	7076	7080	4	16	0	ISIP and 5 min ISIP													
	WASATCH	7166	7170	3	12	50	Slickwater Pad			Slickwater	3,645	3,645	87	87	15.0%	0.0%	0	0		11
	WASATCH	7204	7206	3	6	50	Slickwater Ramp	0.25	1	Slickwater	6,885	10,530	164	251	28.3%	17.2%	4,303	4,303		10
	WASATCH					50	SW Sweep	0	0	Slickwater	0	10,530	0	251	28.3%	0.0%	0	4,303		0
	WASATCH					50	Slickwater Ramp	1	1.5	Slickwater	6,885	17,415	164	415	28.3%	34.5%	8,606	12,909		10
	WASATCH					50	SW Sweep	0	0	Slickwater	0	17,415	0	415	28.3%	0.0%	0	12,909		0
	WASATCH					50	Slickwater Ramp	0.5	1.5	Slickwater	0	17,415	0	415	28.3%	0.0%	0	12,909		0
	WASATCH					50	Slickwater Ramp	1.5	2	Slickwater	6,885	24,300	164	579	28.3%	48.3%	12,049	24,958		0
	WASATCH					50	Flush (4-1/2")				4,534	28,834	108	687				24,958		0
	WASATCH						ISDP and 5 min ISDP					28,834								32
		# of Perfs/stage			43											gal/ft	25,312	25,998	lbs sand/ft	
						11.6											CBP depth	6,946		LOOK
	Totals				248						Total Fluid	355,859 gals		8,601	bbls		Total Sand	335,533		
						2.7						8,473 bbls								
													19.1	tanks				Total Scale Inhib. =	748	

Estimated Total Completion Cost \$283,910

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTSTML-3141-A
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: TRIBAL SURFACE
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1261'FSL, 1248'FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S, 21E		8. WELL NAME and NUMBER: NBU 921-16MT 9. API NUMBER: 4304739362 10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input checked="" type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR HAS PERFORMED THE RECOMPLETE ON THE SUBJECT WELL LOCATION. THE OPERATOR HAS COMPLETED THE WASATCH AND MESAVERDE FORMATIONS, AND COMMINGLED THE NEWLY WASATCH AND MESAVERDE FORMATIONS. THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 04/06/2009 AT 9:00 AM.

PLEASE REFER TO THE ATTACHED RECOMPLETION CHRONOLOGICAL WELL HISTORY.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 4/8/2009

(This space for State use only)

RECEIVED

APR 20 2009

DIV. OF OIL, GAS & MINING

# ROCKIES

## Operation Summary Report

Well: NBU 921-16MT		Spud Conductor: 8/11/2008		Spud Date: 8/12/2008	
Project: UTAH		Site: UINTAH			Rig Name No: GWS 1/1
Event: RECOMPLETION		Start Date: 3/30/2009		End Date:	
Active Datum: RKB @4,841.00ft (above Mean Sea Level)			UWI: NBU 921-16MT		

Date	Time Start-End	Duration (hr)	Phase	Code	Subco de2	P/U	MD From (ft)	Operation
3/30/2009	7:00 - 7:30	0.50	COMP	48		P		HSM. WIND SAFTY. MAKE SURE PIPE IS SECURE IN TBG BOARD.
	7:30 - 15:00	7.50	COMP	31	I	P		RU RIG. BLOW WELL DOWN T/ PROD TANK. FLOWING WELL PSI 55#. PUMP 20 BBLS 2% KCL DOWN TBG T/ CONT WELL. ND WH, NU BOP. RU TBG EQUIP. UNLAND TBG, LD 4 1/16 TBG HNGR. POOH W/ TBG. LD 17 JTS 2 3/8, L-80 & STDBACK 292 JTS 2 3/8, L-80. ND BOP, NU FRAC VALVES. SWI. PUT WELL DOWN SALES LINE FOR NITE.
3/31/2009	7:00 - 7:30	0.50	COMP	48		P		WATER USED 140 BBLS T/ CONTROL. 2 3/8, L-80 LOOKED GOOD NO SCALE @ ALL. HSM. WERE YOU SHOULD HAVE YOUR H2S MONITOR ON YOUR BODY.
	7:30 - 18:00	10.50	COMP	34	I	P		FLOWING WELL PSI 100#. BLOW WELL DOWN T/ PROD TANK. MIRU SCHLUMBERGER W.L.. PU 4 1/2 GR. RIH T/ 9300'. POOH. PU 4 1/2, 10K HALIBURTON CBP. RIH SET CBP @ 9280'. POOH. RIG PUMP T/ CSG, FILL CSG W/ 120 BBLS 2% KCL & PSI T/ 3200# W/ RIG PUMP. MIRU B&C QUICK TEST. CONT PSI T/ 6200#. GOOD TEST. BLEED OFF PSI. RDMO B&C QUICK TEST.
4/4/2009	7:00 -			33	A			STG 1) PU 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH PERF F/ 9246'-50', 3 SPF, 12 HOLES. 9186'-88', 3 SPF, 6 HOLES. 9120'-22', 3 SPF, 6 HOLES. 9067'-72', 3 SPF, 15 HOLES. POOH, MIRU SCHLUMBERGER FRAC SERV. PSI TEST LINES T/ 7200#. GOOD TEST. BLEED DOWN PSI. OPEN WELL 475#. BEG PUMP, BRK @ 4082# @ 5.3 BPM. SD ISIP 3000#, FG .76. BEG FRAC, PUMP 85,071# 30/50 WHITE & TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2950#, FG .75. X-OVER FOR W.L.
								STG 2) PU 4 1/2, 8K HALLIBURTON CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 8870' P/U PERF F/ 8834'-40', 3 SPF, 18 HOLES. 8786'-90', 3 SPF, 12 HOLES. 8752'-56', 3 SPF, 12 HOLES. POOH, X-OVER FOR FRAC CREW. OPEN WELL 1700#, BEG PUMP, BRK @ 3417# @ 5.3 BPM. SD ISIP 2250#, FG .69. BEG FRAC, PUMP 50,237# 30/50 WHITE & TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2850#, FG .75. SWI, SDFN. PREP T/ W.L. STG 3 IN THE :AM.
4/5/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 3000#, TP 1900#, 20/64" CK, 45 BWPH, TRACE SAND, MEDIUM GAS TTL BBLS RECOVERED: 3523 BBLS LEFT TO RECOVER: 5323
								7 AM FLBK REPORT: CP 3050#, TP 2025#, 20/64" CK, 24 BWPH, TRACE SAND, MEDIUM GAS TTL BBLS RECOVERED: 4279 BBLS LEFT TO RECOVER: 4567

## ROCKIES

## Operation Summary Report

Well: NBU 921-16MT		Spud Conductor: 8/11/2008		Spud Date: 8/12/2008				
Project: UTAH		Site: UINTAH		Rig Name No: GWS 1/1				
Event: RECOMPLETION		Start Date: 3/30/2009		End Date:				
Active Datum: RKB @4,841.00ft (above Mean Sea Level)		UWI: NBU 921-16MT						
Date	Time Start-End	Duration (hr)	Phase	Code	Subcode2	P/U	MD From (ft)	Operation
4/6/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 2500#, TP 1700#, 20/64" CK, 22 BWPH, TRACE SAND, 2000 GAS TTL BBLS RECOVERED: 4826 BBLS LEFT TO RECOVER: 4020
4/7/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 2350#, TP 1500#, 20/64" CK, 20 BWPH, TRACE SAND, 2000 GAS TTL BBLS RECOVERED: 5318 BBLS LEFT TO RECOVER: 3528

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER _____		
b. TYPE OF WORK:		NEW WELL <input type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input checked="" type="checkbox"/>	OTHER <b>RECOMPLETION</b>
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP						5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST ML-3141-A	
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078						6. IF INDIAN, ALLOTTEE OR TRIBE NAME: TRIBAL SURFACE	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1261'FSL, 1248'FWL  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:						7. UNIT or CA AGREEMENT NAME: UNIT #891008900A	
						8. WELL NAME and NUMBER: NBU 921-16MT	
						9. API NUMBER: 4304739362	
						10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES	
						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSW 16 9S, 21E	
						12. COUNTY: UINTAH	
						13. STATE: UTAH	
14. DATE SPUDDED: 8/11/2008		15. DATE T.D. REACHED: 10/19/2008		16. DATE COMPLETED: 4/6/2009		17. ELEVATIONS (DF, RKB, RT, GL): 4823'GL	
18. TOTAL DEPTH: MD 10,310 TVD		19. PLUG BACK T.D.: MD 10,150 TVD		20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)  N/A						23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,760		660			
7 7/8"	4 1/2 I-80	11.6#		10,310		1760			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	9,885							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) WASATCH	6,996	7,206			6,996 7,206	0.36	43	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) WSTCH/MESA	7,996	8,120			7,996 8,120	0.36	42	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C) MESAVERDE	8,530	9,250			8,530 9,250	0.36	123	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
6996'-7206'	PMP 853 BBLS SLICK H2O & 39,253# 30/50 OTTOWA SD
7996'-8120'	PMP 1539 BBLS SLICK H2O & 61,787# 30/50 OTTOWA SD
8530'-9250'	PMP 5438 BBLS SLICK H2O & 205,460# 30/50 OTTOWA SD

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

30. WELL STATUS:

PROD

RECEIVED

MAY 18 2009

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 4/6/2009	TEST DATE: 4/8/2009	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 2,048	WATER – BBL: 480	PROD. METHOD: FLOWING
CHOKE SIZE: 20/64	TBG. PRESS. 1,178	CSG. PRESS. 2,261	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED: 4/6/2009	TEST DATE: 4/8/2009	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 2,048	WATER – BBL: 480	PROD. METHOD: FLOWING
CHOKE SIZE: 20/64	TBG. PRESS. 1,178	CSG. PRESS. 2,261	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED: 4/6/2009	TEST DATE: 4/8/2009	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 2,048	WATER – BBL: 480	PROD. METHOD: FLOWING
CHOKE SIZE: 20/64	TBG. PRESS. 1,178	CSG. PRESS. 2,261	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	1,674				
BIRDS NEST	1,986				
MAHOGANY	2,496				
WASATCH	5,100	8,048			
MESAVERDE	8,064	10,309			

## 35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE

DATE 5/11/2009

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940